

Government of the People's Republic of Bangladesh
Office of the Executive Engineer
PWD Division, Chapainawabganj.
Phone:-0781-62067, Fax-0781-51743
Email: ee_chpai@pwd.gov.bd

Memo No-620


Date:-03/10/2016

CORRIGENDUM NOTICE

This is to inform to all concerned that the following correction in the invitation for Tender No-03(Civil)/2016-2017 vide this office Memo No- 169, Date: 28/08/2016 for Construction of Chief Judicial Magistrate Court Building of 64 District Headquarter in Bangladesh. (1st Phase) (2nd revised) 1(One)at Chapainawabganj. (Sub-head : Vertical Extension of Chief Judicial Magistrate Court building from 4th Floor to 7th Floor including Civil, Sanitary, Electrical & ancillary works) is made:

SI No/ Indicators	Description	As Printed	To be replaced as
Notice SI No-16	Eligibility of Tenderer	(H) If tenderer's quoted rate exceeds 10% above or less of official cost estimate then tender will be Non-Responsive according to the latest amendment of section 31 of PPA 2006, Act No-24	উপ-পরিচালক, পরিকল্পনা মন্ত্রণালয়, বাস্তবায়ন পরিবীক্ষণ ও মূল্যায়ন বিভাগ, সেন্ট্রাল প্রকিউরমেন্ট টেকনিক্যাল ইউনিট, ঢাকা-১২০৭ এর দপ্তর স্মারক নং- ২১.৩৬৪.০০২.০২.১৫.৪৬৪.২০১৪.১৭৫৭ তারিখ- ০২/১০/২০১৬ খ্রিঃ মোতাবেক $\pm 10\%$ এর শর্তটি বাতিল করা হলো।
Notice SI No- 10	Tender Last Selling date	05/10/2016 during office hour.	24/10/2016 during office hour.
Notice SI No-11	Tender last Submission date & time	06/10/2016 up to 12.00 Noon	25/10/2016 up to 12.00 Noon
Notice SI No-12	Tender Opening date and time	06/10/2016 at 3.00 P.M.	25/10/2016 at 3.00 P.M.
	Eligibility of Tenderer	Not Mentioned	যৌথ অংশীদারিত্বের মাধ্যমে অংশগ্রহণের ক্ষেত্রে JVCA সংক্রান্ত CPTU এর জারিকৃত পরিপত্র নম্বরঃ আইএমইডি/সিপিটিইউ/নীতিনির্ধারণ/২৬২/২০১১.১১৯২ তারিখঃ ২৬/০৭/২০১৫ আবশ্যিকভাবে অনুসরণ করতে হবে।
BOQ Item No- 10	PART-'B' Civil Works	12 mm thick finished and laying thickness 14.5 mm cast in situ mosaic work on floor with one part of 10 mm machine crushed well graded dust free and properly washed marble chips and one part of mixture containing 100% white cement including preparation of mix and laying the same over minimum 25 mm thick artificial patent stone flooring with brick-chips (1:2:4) including making suitable panel, compacting, curing at least for 7 days, cutting with pumic stone (No. 40, No. 80, No. 120)/ mosaic cutting machine and finishing with Minar stone including breaking brick chips screening, spreading oxalic acid, washing mosaic chips and supply of all necessary materials and water, electricity and other charges in all respect accepted by the Engineer. (Cement: CEM-II/A-M)	12 mm thick finished and laying thickness 14.5 mm cast in situ mosaic work on floor with one part of 10 mm machine crushed well graded dust free and properly washed marble chips and one part of mixture containing 100% white cement including preparation of mix and laying the same over minimum 25 mm thick artificial patent stone flooring with brick-chips (1:2:4) including making suitable panel, compacting, curing at least for 7 days, cutting with pumic stone (No. 40, No. 80, No. 120)/ mosaic cutting machine and finishing with Minar stone including breaking brick chips screening, spreading oxalic acid, washing mosaic chips and supply of all necessary materials and water, electricity and other charges in all respect accepted by the Engineer. (Cement: CEM-II/A-M) With Pakistani chips and glass strip

All others terms and conditions will remain unchanged. The Corrigendum will be a part and parcel of the said tender


 (Md. Masud Rana)
 Executive Engineer
 PWD Division, Chapainawabganj.